

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Alcona County  
 Remonumentation  
 Liber 1 Page 216  
**RECORDED**

For corners in Alcona Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |   |            |   |           |            |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey                | T | <u>28N</u> | R | <u>8E</u> | M-6        |
|                                      | T | <u>28N</u> | R | <u>9E</u> | <u>A-6</u> |
|                                      | T | _____      | R | _____     | _____      |
|                                      | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____      |
|                                      | S | _____      | T | _____     | _____      |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____      |
|                                      | S | _____      | T | _____     | _____      |

APPROVED LAND CORNER  
 F A 345 of 1990  
 ALCONA COUNTY  
 Date 11-21-96  
 Register of Deeds

Nov 21 1 50 PM '96

*Doris A. Benthien*  
 REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel T. Kibbe, in a field survey on June 20, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1839: G.L.O. Survey by Lewis Clason - set post & referenced: Hemlock 12 - S 23 W - 14 / Hemlock 12 - N 58 W - 36.  
 1994: MDOT F-41 Alignment by Cliff Lindgren - nail & brass tag, referenced.  
 1995: Surveys by Earl Lewis - existing buried iron, raised with nail, referenced.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1996: Found nail with tag in C/L F-41.

This corner position is compatible with local surveys and agrees with MDOT records. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**SURVEY & REMONUMENTATION**

DEC 16 1996

COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1996: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.

- Referenced:  
 East - 41.40' - fd. MDOT Tag in fence post  
 West - 100.50' - fd. MDOT Tag in fence post  
 N 42° E - 75.32' - fd. MDOT Tag in fence post  
 S 67° W - 78.36' - set N/Tag in 18" Red Pine



Signed by *Daniel T. Kibbe*

Date October 16, 1996

Surveyor's Michigan License No. 37278