

*Sept 17*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona  
(County)

Located In:

Corner Code #

County Rep 1717

Date 9-26-96

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

RECORDED

SEP 24 2 41 PM '96

*David B. Guthrie*  
REGISTERED SURVEYOR  
MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 28N R 8E  
T 28N R 9E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Section S \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ R \_\_\_\_\_

- M-12
- A-12
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on July 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced  
Hem. 10 - S58W - 39 / Beech 10 - N351/2W - 28
- 1994: Survey by Lewis and Lewis - Set 1/2" Iron Rod using 1/8 line information.  
Referenced: N62E - 12" W.Pine - 53.71 Feet  
S17E - 12" W.Pine - 70.70 Feet  
S12W - P. Pole - 170.49 Feet  
N15W - P. Pole - 136.49 Feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1/2" Iron Rod with cap #27452 in the North South road centerline.

SURVEY &  
REMONUMENTATION  
  
DEC 16 1996  
  
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Set a 1/2" Iron Rod with an Aluminum Cap stamped to identify the corner 6" below the road surface.  
Referenced: N67°E - 15" R. Pine - 53.85 Feet  
S09°E - 12" W. Pine - 70.62 Feet  
N09°W - Utility Pole - 136.44 Feet  
S22°W - Utility Pole - 170.46 Feet



Signed by *David B. Guthrie*

Date Sept. 17, 1996

Surveyor's Michigan License No. 22435