

FEB 19 1999

1998 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION For corners in

Alcona (County)

Located In:

Corner Code #

1. Public Land Survey

T 28N R 9E

F-7

T R

Alcona Twp.

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

Alcona County Remonumentation Liber Page 323

Filed for Record in ALCONA COUNTY MICHIGAN DORIS A GAUTHIER On 12-17-1998 At 05:34:50 pm. LAND CORNER 9.00

APPROVED LAND CORNER P A 345 of 1990 ALCONA COUNTY

Date 10/21/98 County Rep D. B. Tom

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 7, column F.

I, Thomas L. Fabis, in a field survey on May 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey Thos. Pattison Set 1/4 Sec. Post & referenced: Hem 16 S46E 44, do 9 N67W 35.
1985: LCRC L.1 P.189 and Survey L.200 P.834 David Guthrie Set Forest Service Conc. Mon. 12" below surface. Raised with nail & referenced.
1987: Survey L.218 P.683 Duane MacNeill Found Conc. Mon.
1988: Survey L.218 P.684 Duane MacNeill Found Conc. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Found Forest Service Conc. Mon. with Brass cap in the centerline of Black River Road intersection with fence to the North and Found Carsonite Post S5W 48.4'

The position of this corner is compatible with the local and Forest Service Surveys mentioned above and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Set monument box around existing Forest Service Conc. Mon. because the existing Conc. Mon. was below the bottom of the monument box, a 1/2" iron rod capped with a 3" dia. brass cap stamped to identify the corner was placed over the conc. monument. Set tag in the following witnesses:
Fe. Cor. Post North 33.53'
8" Oak N18W 43.60'
9" Birch S22E 68.95'
4" Cedar S15W 55.58'

Signed by

Thomas L Fabis

Date December 11, 1998

Surveyor's Michigan License No. 31591

