

FEB 19 1999

1998 ALCONA COUNTY REMONUMENTATION CORNER



SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28NR 9E</u>	<u>J-7</u>
	T <u> R </u>	<u>Alcona Twp.</u>
	T <u> R </u>	_____
	T <u> R </u>	_____
2. Property Controlling in Section	S <u> T </u>	_____
	S <u> T </u>	_____
3. Miscellaneous Property in Sec.	S <u> T </u>	_____
	S <u> T </u>	_____

Alcona County Remonumentation 327 P. 388

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1998 At 05:35:01 pm.
LAND CORNER 9.00

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 10/21/98
County Rep D. J. B. [Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on May 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7										●			
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey Thos. Pattison Set post & referenced: Cedar 6 N25W 22, Spruce 5 S30E 30.
- 1961: River's Bend Plat L.1 P.193 James Scott Visits corner.
- 1966: River's Bend No. 2 Plat L.2 P.44 Robert Paquette Meas. to 1/8 corner East.
- 1970: Feldhauser Survey L.145 0.853 Edward LaCross Visits corner.
- 1988: LCRC L.1 P.339 & Survey L.224 P.835 & 837 Robert Mitchell Found bent cabin spike on shoulder of road. Fits S.P. position. Set Forest Service Conc. Mon. in its place & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1998: Found 60 Penny nail over Forest Service Conc. Mon. with brass cap 12.2 feet North of Black River Rd. centerline and found the following witnesses:
Carsonite Post North 13.2'
60 Penny nail in 6" Ash N20E 54.32'
60 Penny nail in 8" Birch S15E 61.38'
60 Penny nail in 11" Ash S08E 66.49'
Nail in P. Pole N32W 39.51'

The position of this corner is compatible with local and Forest Service surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Existing Forest Service Concrete Mon. with Brass cap below surface of gravel shoulder 12.2 feet North of Black River Road center line. Witnesses are:
Carsonite Post North 13.2'
60 Penny nail in 6" Ash N20E 54.32'
60 Penny nail in 8" Birch S15E 61.38'
60 Penny nail in 11" Ash S08E 66.49'
Nail in P. Pole N32W 39.51'

Signed by Thomas L. Fabis Date December 11, 1998
Surveyor's Michigan License No. 31591

