

APR 21 1994

001 PAGE 37

COMMISSION

1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona

(County)

Located In:

Corner Code #

1. Public Land Survey

T 28 N R 9 E

K - 11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED

Remon Liber 1 Page 37

DEC 21 4 22 PM '93

Doris A. Guthrie  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 3, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by U.S. Deputy Surveyor

1973 - Recorded survey by E. LaCross LS# 173  
Notes: "Found iron & 4" Hub" for K-11

Witnesses:

Tam 10 S32W 14  
Cedar 9 N18E 21

Witnesses:

N09°E 14.25' 36" Ash  
East 46.6' 13" Cedar

\* Witnesses are best interpretation of illegible survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1975 - J. Scott LS # 8318, recorded K - 11  
Found cedar stake, 1/2" iron rod and 1" pipe with cap #17698 (transcription error?)

1987 - D.R. MacNeill recorded survey  
Found 4" x 4" cedar stake and 1" capped pipe for K-11.

1993 - Remonumentation crew found 1" pipe with cap and drove 1/2" re-rod into said pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to 1/2" re-rod driven into 1" pipe.

Witnesses:

N 10° E 15.25 12" Cedar  
Due East 46.78 18" Cedar  
N 85° W 69.90 6" Twin Maple  
S 20° W 24.41 8" Maple

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license \$19237.

Signed by

*Duane R. MacNeill*

Date December 16, 1993

Surveyor's Michigan License No. 19237

