

SURVEY & REMONUMENTATION

APR 21 1994

1993 ALCONA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>9E</u>	<u>K - 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
Remon Liber 1 Page 38

DEC 21 4 22 PM '93

Doris A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set as an even split of 80.00 chains by Lewis Clason, U.S. Deputy Surveyor.

Witnesses:

Cedar 7 N14W 11
Do 6 S33E 24

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence of corner or accessories found.

Tom Fabis, P.S. #31591 found in the Fall of 1993 a 4" concrete monument below grade and under a fallen stump.

Witnesses:

N 35° E 36.59 6" Maple
N 74° E 26.10 6" Balsam
S 80° W 34.06 7" Balsam
S 30° E 61.70 7" Cedar

1993 - Remonumentation crew found 4" concrete monument as noted by Tom Fabis above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to re-rod extending from concrete monument.

Witnesses:

N 35° E 36.62 6" Maple
N 74° E 26.14 6" Balsam
S 80° W 34.01 7" Balsam
S 30° E 61.66 7" Cedar

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237.

Signed by Duane R MacNeill
Surveyor's Michigan License No. 19237

Date December 16, 1993

