

**SURVEY &
REMONUMENTATION**

APR 21 1994

001 PAGE 39
1993 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in
Alcona
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>9E</u>	<u>K - 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Remon Liber 1 Page 39

DEC 21 4 22 PM '93

Doris A. Bantline
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Duane R. MacNeill, in a field survey on August 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - Set by Lewis Clason, U.S. Deputy Surveyor.

1977 - Recorded survey by D.R. MacNeill #19237. Found 4"x4" concrete monument.

Witnesses:

Tam 20 N 41½ W 28
W. Birch 9 N 30½ E 11

Witnesses:

N 05° E 17.55' 8" Cedar
N 45° W 18.37' 8" Cedar
S 30° W 13.19' 6" Ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories.

1993 Remonumentation crew found in this location a 4"x4" concrete monument as described above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Alcona County Remonumentation Aluminum Cap, appropriately stamped, secured to re-rod extending from concrete monument.

Witnesses:

N 05° E 2.00 12" Cedar
N 45° W 19.00 12" Cedar
S 55° E 47.31 12" Cedar
S 45° W 27.96 10" Cedar

Witnesses were freshened as necessary; nails replaced with duplex nails bearing a brass washer stamped license #19237

Signed by *Duane R. MacNeill*
Surveyor's Michigan License No. 19237

Date December 16, 1993

