

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 9. E. . .

Alcona COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 and 4 . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap . . .

WITNESSES TO CORNER . . .

5" W. Birch - S28E - 49 links
5" Aspen - S74W - 16 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between Section corners by Forestry Division survey crew while making a survey in this area. Found an old square stake, not scribed, in vicinity but could not determine its original position. It may have floated several feet. No evidence of OBTs or new witnesses.

Corner was placed and witnessed April 12, 1957.

SURVEYORS SEAL

SIGNED Billy J. Buckle DATE 5/3/57
REGISTERED LAND SURVEYOR