

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 9 E.

Alcona

COUNTY

DESCRIPTION OF CORNER Corner common to Sections 3, 4, 9, 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

12" R. Pine - S52E - 64½ links  
5" W. Birch - S57W - 32½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Corner was established by double proportionate measurement between corners 1 mile north, south, east, and west. No evidence of the original BTs could be found. See map and minutes of survey for other information. A 4" diam. concrete monument is 49 links north and 96 links west.

Corner was placed and witnessed April 11, 1957.

SURVEYORS SEAL

SIGNED Pilly D. Buckler  
REGISTERED LAND SURVEYOR

DATE 5/3/57