

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 NR 9 E . . .

Alcona COUNTY

DESCRIPTION OF CORNER Corner common to Sections 9, 10, 15, 16

DESCRIPTION OF CORNER MONUMENT 1/2"x36" pipe, below surface

WITNESSES TO CORNER

No trees near worth noting

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. This point was established at the intersection of the centerlines of a county road from the south and an old road grade east across a marshy bog. Nearby residents have accepted and used this as the corner, and the length between 15 and 16 from the center of the Black River road checks within 13 links a measurement recorded by Freer in 1912, but his Tamarack witness could not be found--possibly removed in grade construction.

Corner was set April 10, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/3/57
REGISTERED LAND SURVEYOR