

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 NR. 9 E . . .

Alcona COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side Section 3, T28N R9E

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

<u>9" W. Ash</u>	<u>-</u>	<u>S64E</u>	<u>-</u>	<u>24 links</u>
<u>6" W. Ash</u>	<u>-</u>	<u>S52W</u>	<u>-</u>	<u>36 links</u>

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Corner was established by proportionate measurement between section corners of Section 3, T28N R9E

1/4 corner for Section 34, T29N R9E is 36 links west.

Corner was placed and witnessed April 12, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/9/57
REGISTERED LAND SURVEYOR