

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 9. E. . .

Alcona COUNTY

DESCRIPTION OF CORNER Closing corner common to Sections 3 & 4 on
north boundary of T28N R9E.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" W. Birch	-	86W	-	71 $\frac{1}{2}$ links
9" W. Ash	-	887W	-	30 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey crew
while making a survey in this area. Corner was established in reference
to the corner to Sections 33 & 34, T29N R9E as per government record.
No BTs were noted in the government survey at this corner.

Corner to Sections 33 & 34, T29N R9E is 96 links west.

Corner was placed and witnessed April 10, 1957.

SURVEYORS SEAL

SIGNED Rilly D. Buchler DATE 5/2/57
REGISTERED LAND SURVEYOR