

pg. 2

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona (County) Located In: Corner Code # 1. Public Land Survey T 28N R 8E T 28N R 9E T T T T 2. Property Controlling in Section S T R S T R 3. Miscellaneous Property in Section S T R S T R

Nov 21 1 49 PM '96

Jane A. Bantier REGISTER OF DEEDS ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 1-13. Row 12, column M contains a small circle.

I, Daniel T. Kibbe, in a field survey on October 16, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey by Lewis Clason - set post & referenced: W. Pine 13 - S 45 1/2 W - 25 / Y. Pine 20 - N 36 1/2 W - 24. 1913: County Survey by Andrew Freer - Piece of slay shoe 36" long, 3" wide, referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: No monumentation found. Corner position established by single proportionate method.

SURVEY & REMONUMENTATION

JUN 29 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.

- Referenced: S 48° W - 60.84' - set N/Tag in Power Pole N 85° W - 58.35' - set N/Tag in 20" Poplar N 45° W - 82.52' - set N/Tag in 10" Birch S 84° E - 60.52' - set N/Tag in 7" Birch



Signed by [Signature]

Date October 16, 1996

Surveyor's Michigan License No. 37278