

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alger

(County)

Located In:

Corner Code -##

- | | | |
|------------------------------------|----------------------------|-----------|
| 1. Public Land Survey | T <u>44W</u> R <u>21W</u> | <u>14</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>1</u> T _____ R _____ | <u>14</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith Sackett, in a field survey on May 8, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>14</u>	<u>14</u>
One quarter corner common to sections 10 and 11. Original monument and accessories not found.	South one-sixteenth corner common to sections 1 and 6. Not set in original survey, no evidence of subsequent est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>14</u>	<u>14</u>
Restored from Alger Co. Road Commission notes.	Established midway and on line between corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>14</u>	<u>14</u>
DNR.	DNR monument.
Pk. in power pole North 32.65'	5" cedar N13E 109.2' BT
NBT	6" spruce S48E 75.3' BT
Pk. in guard post for	4" aspen S47W 41.45' BT
telephone box N64E 64.45' NBT	4" bals of gilead N32W 44.25'
10" cedar S66W 83.55' NBT	BT

Signed by

Keith S Sackett

Date

Surveyor's Michigan License No. _____

19006

