

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>21W</u>	<u>K2</u>
	T _____ R _____	<u>K2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S <u>2</u> T _____ R _____	<u>7</u>
	S _____ T _____ R _____	<u>14</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on May 1, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>K2</u> Quarter corner common to Sections 1 and 2.	<u>K2</u> Quarter corner common to Sections 1 and 6. Original monument and accessories not found.	<u>7</u> North one-sixteenth corner common to Sections 1 and 2. Not set on original survey, nor subsequently, apparently.	<u>14</u> South one-sixteenth corner common to Sections 1 and 2. Not set on original survey nor subsequently, apparently.
---	--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K2</u> Restored by single proportionate measure between the northeast and southeast corners of Section 2.	<u>K2</u> Restored by single proportionate measure between northeast and southeast corners of Section 1.	<u>7</u> Established by single proportionate measure between the northeast and east quarter corners of Section 2.	<u>14</u> Set midway and on line.
---	---	--	--------------------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K2</u> DNR monument. 5" red maple N29E 38.2' 5" red maple S30E 31.65' 12" spruce S73W 14.95' 7" black cherry N47W 35.1'	<u>K2</u> DNR monument. 8" basswood N18E 66.6' 5" spruce S29E 35.0' 4" balsam S27W 70.15' 4" red maple N25W 91.6'	<u>7</u> DNR monument. 6" red maple N20E 41.15' 11" white pine S27E 20.0' 5" white pine S16W 16.5' 4" red maple N18W 10.6'	<u>14</u> DNR monument. 6" white pine N13E 43.8' 11" cherry S46E 61.1' 10" red maple S24W 54.6' 8" red maple N59W 63.95'
---	--	---	---

Signed by

Keith Sackett

Date

June 13, 1991

Surveyor's Michigan License No.

19066

