

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

7	<u>Alger</u>	Located In:	Corner Code -#
	(County)		
1.	Public Land Survey	T 44N R 21W	16
		T R	16
		T R	
		T R	
2.	Property Controlling in Section	S 3 T R	16
		S 14 T R	9
3.	Miscellaneous Property in Sec.	S T R	
		S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith Sackett, in a field survey on May 14, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2		5	4	3								
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I6	J6	16	9
Quarter corner common to sections 14 and 15. Original monument and accessories not found.	Center quarter corner of Section 14. Not set in original survey no evidence of subsequent establishment.	East one-sixteenth corner common to sections 3 and 10. Not set on original survey nor subsequently, apparently.	Center East one-sixteenth corner of Section 14. Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I6	J6	16	9
Set midway and on line.	Set at the intersection of the north-south and east-west quarter lines.	Set midway and on line.	Set midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I6	J6	16	9
DNR monument. 6" basswood N37E 62.95' 12" cedar North 60.2' 14" cedar N37W 55.6'	DNR monument. 6" red maple triple N17E 49.15' 5" sugar S37E 64.7' 5" balsam S28W 30.15' 10" red maple N07W 52.8'	DNR monument. 7" sugar maple N12E 28.2' 10" cedar S41E 15.95' 11" cedar S81W 26.55' 12" cedar W25W 44.4'	DNR monument. 5" sugar maple N12E 49.4' 5" sugar maple S38E 58.95' 6" sugar maple S18W 38.9' 8" sugar maple N17W 53.3'

Signed by Keith L. Sackett Date _____

Surveyor's Michigan License No. 19006

