

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>21</u> E. W.	<u>L-9, M-9, M-10</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Rabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 16 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-9 N $\frac{1}{4}$ corner - Sec. 25; wood post - cedar 10 - S40°E - 13 lks.; cedar 10 - N10°W - 10 lks.
Searched for but found nothing.
- M-9 N.E. Section corner - Sec. 25; wood post - cedar 10 - N50°E - 17 lks.; Do 10 - N40°W - 9 lks.
- M-10 East $\frac{1}{4}$ corner - Sec. 25; wood post - Tam. 7 - N60°E - 20 lks., Do 8 - N72°W - 17 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-9 Set M.P.O.L. between the N.E. and N.W. section corners of Sec. 25.
- M-9 Set from two cedar stumps - bearings and distances exact for both cedar O.B.T.S. - N.E. one has several axe blazes but no scribe marks visible. Both stumps down and in poor condition. This position fits well with corners north, south and west.
- M-10 Found old sq. cedar post with stones piled around it. Old field notes by R. Schmeling R.L. indicate this post to be "40.12" north of the S.E. corner of Sec. 25. We find it to be 40.01 south of the N.E. corner of Sec. 25. There is a tam. stump in place for the N.W. OBT, showing some signs of having been blazed but no scribe marks. There is a depression where the N.E. O.B.T. should be. Replaced sq. post with a D.N.R. monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- ALL - 1" pipe, 4" aluminum cap.
- L-9 8" cedar - N19°E - 8.0'; 7" cedar - N53°W - 14.6'; 10" cedar - S6°W - 25.7'; 10" cedar - S73°E - 13.0'
- M-9 5" cedar - S42°E - 13.85'; 4" s. maple - S17°W - 28.20'; 3" s. maple - N57°W - 15.30', 4" s. maple - N60°E - 13.65'
- M-10 8" w. birch - S5°W - 26.65'; 8" b. spruce - N41°W - 31.65'; 10" b. spruce - N19°E - 32.40', 9" cedar - N55°E - 36.38'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Rabbitt CHIEF OF SURVEY PARTY DATE 9-7-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558