

Alger County

OK
R. 11/1/83

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44N</u> N. S., R. <u>21W</u> E. W.	K-4 & K-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-4 - East 1/4 Cor. of Sec. 11; Wood Post - Sugar 20 - S86°E - 26 Lks.; W. Pine 12 - N72°W - 11 Lks.
- K-5 - S.E. Sec. Cor. of Sec. 11; Wood Post - Sugar 22 - S50°E - 35 Lks.; Cedar 10 - N45°W - 28 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-4 - Found 2" pipe with the top broken off. This looks like the bottom of one of Geo. Depew's Mons. Measurement and alignment North & South fits very well.
- K-5 - Found part of iron shaft 30" long. Not of record but Mea. and alignment N & S fit very well. Replaced shaft w/D.N.R. Mon.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-4 - 2" pipe flush with ground; 12" Maple - N73°E - 61.8'; 5" Bl. Cherry - S55°E - 33.4'; 8" Bl. Cherry - S20°W - 35.9'; 11" Bl. Cherry - N24°E - 70.4'.
- K-5 - D.N.R. Monument; 10" Spruce - S18°W - 13.35'; 6" Maple - S39°E - 18.0'; 6" Apple - N64°E - 17.8'; 5" Maple - N25°W - 21.1'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____