

# Alger County

## LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>44</u> N. S., R. <u>21</u> E. W.		<u>K-7</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 16, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 7 - N.E. Sec. Cor. of Sec. 23; pipe and brass cap Mon. was set here by Geo. Depew in 1916. No N.B.T.s recorded but his notes indicate both O.B.T.s were in place at that time.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 - Depew's Mon. was found lying beside a woods road near the East 1/4 Cor. position of Sec. 23, R. Borak, D.N.R. Forester, in 1954. Again in 1958 it was seen and noted lying beside the road in the vicinity of the East 1/4 Cor. of Sec. 23 by Bob Schmeling R.L.S. In 1970 Frank Bray Dist. and Surveyor for the D.N.R. found this same Mon. set shallowly in the apparent right position for the Sec. Cor. Frank was not aware that this Mon. had been pulled, carried away and then returned to the area. He, therefore, accepted it as being Depew's Sec. Cor., witnessed it as found and recorded it. Later measurements by D.N.R. foresters and subsequently by myself, proved this Mon. was not in its proper position. No longer being able to determine Depew's position exactly I have reset his Mon. by double prop. measurement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 7 - 2" pipe w/3" Brass Cap; 7" Maple - N51°E - 15.7'; 7" Maple - S21°E - 20.5'; 6" Ironwood - S26°W - 19.0'; 11" Maple - N36°W - 38.4'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_