

Alger County

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--: LOCATED IN--: CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 44N N. S., R. 21W E. W. K-6
2. PROPERTY CONTROLL- 14 ,T. 44N N. S., R. 21W E. W. 7 & 14
ING IN SECTION
3. MISCELLANEOUS N. E.
PROPERTY IN SECTION ,T. S., R. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-6 - East 1/4 Cor. of Sec. 14; Geo. Depew about 1915 set pipe with brass cap. No N.B.T.s recorded.
7 - North 1/16 Cor. on the East Sec. line of Sec. 14; not previously established.
14 - South 1/16 - on East boundary of Sec. 14; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-6 - Made thorough search for Depew's Mon. with magnetic locator - found nothing. Probably destroyed by road construction. Re-set by Prop. Mea. N. & S. and about 5' East of the centerline of gravel road North, as affirmed by longtime local residents Kate Wiltsie and Conrad Walls. Cor. falls in line with centerline of Co. Rd. West.
7 - Set M.P.O.L. between the N.E. Sec. Cor. and the E. 1/4 Cor. of Sec. 14.
14 - Set M.P.O.L. between the E. 1/4 Cor. and the S.E. Sec. Cor. of Sec. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-6 - D.N.R. Mon.; 4" Maple - S20°W - 92.2'; 12" Balsam - S31°W - 50.8'; 6" Maple - S12°E - 52.7'; Power Pole - N42°E - 42.2'.
7 - D.N.R. Mon. Flush with ground; 7" Ironwood - N88°E - 35.0'; N.E. Cor. Hse. FDTN - S78°W - 89.5'; S.e. Cor. Hse. FDTN. - S62°W - 102.1' Ctr. of 5" well pipe - S86°W - 111.7'; Centerline of N-S Road - West - 21'.
14 - D.N.R. Mon.; 5" Sugar Maple - S46°W - 14.60'; 9" Sugar Maple - N31°W - 16.75'; 6" Bl. Cherry - N5°E - 25.25'; 6" (Twin) Sugar Maple - S58°E - 36.40'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.