

Alger County

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Table with 3 columns: FOR CORNERS OF--, LOCATED IN--, CORNER CODE NUMBER. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section, Lot No., and Private Claims.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 - North 1/4 Cor. of Sec. 24; Wood Post - Sugar 18" - S16°W - 15 Lks.; Sugar 10" - N49°E - 20 Lks.
1 - W 1/16 Cor. on the North Sec. line of Sec. 24; not previously established.
2 - East 1/16 Cor. on the North Sec. line of Section 24; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 - Set M.P.O.L. Between the N.E. & N.W. Sec. Cors. of Sec. 24.
1 - Set M.P.O.L. between the N 1/4 Cor. and the N.W. Sec. Cor. of Sec. 24.
2 - Set M.P.O.L. between the North 1/4 Cor. and the N.E. Sec. Cor. of Sec. 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 - D.N.R. Mon.; 5" Aspen - S56°W - 3.55'; 5" Balsam - N52°W - 29.8'; 10" Maple - N05°E - 32.95'; 6" Aspen - N61°E - 27.35'
1 - D.N.R. Mon.; 9" Sugar Maple - S48°W - 16.1'; 5" Sugar Maple - N57°W - 24.1'; 10" Sugar Maple - N16°E - 14.8'; 4" Sugar Maple - N59°E - 24.6'.
2 - D.N.R. Mon.; 3" B. Spruce - N20°E - 25.4'; 5" B. Spruce - S75°E - 24.6'; 9" B. Spruce - S15°E - 23.5'; 14" B. Spruce - S64°W - 13.7'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____ CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____ MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____