

Alger County

24
12-11-83
10-15-83

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44N N. S., R. 21W E. W.	I-7, K-8, J-7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 - N.W. Sec. Cor. of Sec. 23; Wood Post - Cedar 8" - S45°E - 9 Lks.; Cedar 10" - N34°W - 16 Lks.
- K-8 - East 1/4 Cor. of Sec. 23, Wood Post - Sugar 18" - S30°E - 28 Lks., Sugar 4" - N69°W - 9 Lks.
- J-7 - North 1/4 Cor. of Sec. 23; Wood Post Cedar 12" - S45°E - 12 Lks.; Sugar 12" - N20°W - 19 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-7 - Found cedar post flattened on one side w/ Sec. numbers painted on it and the point of an older stake beside it. A Cedar stump with scars to fit upper & lower face is in place for the N.W. C.B.T. Stream call 90 Lks. South fits exactly and stream call West fits also. From original survey notes the stream call West is on the random line which was 52 Lks. South of this Sec. Cor. and calls for the stream at 75 Lks. West. This relationship fits correctly.
- K-8 - Set M.P.O.L. between the N.E. & S.E. Sec. Cors. of Sec. 23 - No sign of original bearing trees.
- J-7 - Set M.P.O.L. between the N.W. and N.E. Sec. Cors. of Sec. 23. No sign of original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7 - D.N.R. Mon.; 6" Cedar - S1°E - 17.1'; 6" Cedar - S77°W - 7.6'; 4" Cedar - N40°W - 16.4'; 4" Cedar - N45°E - 3.3'.
- K-8 - D.N.R. Mon.; 4" Maple - N35°E - 5.4'; 7" Maple - S82°E - 9.65'; 11" Maple - N03°W - 27.8'; 8" Maple - S62°W - 33.8'.
- J-7 - D.N.R. Mon.; 12" Sugar Maple - S32°W - 18.20'; 7" Sugar Maple - S71°W - 23.90'; 5" Sugar Maple - N7°E - 12.90'; 5" Sugar Maple - S57°E - 7.10'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____