

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 22 W


Alcona COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 20, 21, 26 and 27

CORNER MONUMENT 1 1/2" galvanized pipe with 3-inch brass cap O.L.D. dated Sept. 20, 1917

DATE MONUMENT PLACED AND WITNESSED Monument left as found. Witnessed May 3, 1962

WITNESSES TO CORNER..... Elm 6 N 25 E 10.5 links



Elm 13 S 40 E 25.5 links

Elm 17 S 60 W 73.5 links

AND Yellow Birch 14 N 8 W 49.0 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. **This corner monument was apparently set in 1917 from original B.T. or B.T.'s. The cedar B.T. had been sawed off at bottom of upper face probably 40 years ago. The lower face was still plain with some scribe marks distinct. The other original B.T. (spruce) had completely rotted away. Monument checked with cedar B.T. Left monument as found and scribed four new bearing trees and set post next to monument.**

SURVEYOR'S SEAL

SIGNED _____ DATE _____

REGISTERED LAND SURVEYOR