

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>44</u> N. <u>9</u> R. <u>22, 23</u>		<u>K-12, M-12</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. _____ E. _____ S., R. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 9 19 73 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-12 Woodpost:

Cedar 14 S87 1/2° W 27 links
 Spruce 10 N80° E 27 links

M-12 Woodpost:

Cedar 7 N33° W 24 links
 Cedar 8 S68° E 16 links

Subsequent Monument:
 woodpost

Subsequent Monument:
 woodpost

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-12 This corner was replaced from point of rotted woodpost and an original B.T. decay but partially green (Cedar 14 S87 1/2° W 27 links) Rotted stump bottom N80 E 27 links may have been other B.T.

M-12 This corner was replaced from three points of rotted woodposts and an original B.T. (Cedar 8" S68° E 16 links). This B.T. has both upper and lower faces with scribe marks and is green and growing.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Both: 1" iron pipe with 4" aluminum cap. All bearings are magnetic.

K-12

8" Cedar (1/8) (NBT) N52° E 11.9'
 9" Cedar (1/8) (NBT) S01° E 17.8'

M-12

14" Cedar (1/8) (NBT) N81° E 7.8'
 12" Cedar (1/8) (NBT) N87° W 4.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 11-1-73
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575