

1. Public Land Survey, T 45N R 21W H-3, I-3.
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**ALGER
CO.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, David Babbitt, in a field survey on 10/22&23, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3. South 1/4 cor. of Section 3. Wood Post. Sugar 18" S41°W 14 Lks.
 DO 20" N64°E 14 Lks.

I-3. SE section cor. of Section 3. Brass capped monument. Set by Geo. Depew.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3. Set in $\frac{1}{2}$ of E-W road and in line with old fences north and south.

I-3. Set in $\frac{1}{2}$ of E-W road and in line with old fence south. Depew's monument could not be found. I believe FE was set by Depew's survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3. D.N.R. Monument 4" Balsam Fir S8°E 40.7'
 6" Sugar Maple S35°E 56.55'
 3" Cedar N19°W 59.2'
 9" Cedar N61°E 99.3'

I-3. D.N.R. Monument 8" Tam. N12°E 50.5'
 8" Tam. N36°W 64.8'
 20" W. Pine S44°E 56.2'
 4" Hemlock S22°W 53.0'

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No.

RLS 21558