

1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S 11 T 45N R 21W 14. 7. 12. 4
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**ALGER
CO.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 5/22 & 11/25, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

14. S 1/16 cor. on East section line of Section 13. Not prev. est.

7. N 1/16 cor. on East section line of Section 11. Not prev. est.

12. South 1/16 cor. of Section 11. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

14. Set M.P.O.L. between the East 1/4 cor. and the SE sec. cor. of Section 11.

7. Set M.P.O.L. between the East 1/4 cor. and the NE sec. cor. of Section 11.

12. Set M.P.O.L. between the South 1/4 cor. and the center of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14. D.N.R. Monument 6" Cedar S51°W 9.1' 20" Cedar N12°E 19.4'
 14" Spruce S40°E 4.1' 6" B. Ash N20°W 22.8'
 (Corner lies in stream.)

7. D.N.R. Monument 5" R. Maple S41°E 26.2' 9" Black Cherry N54°W 16.3'
 7" Black Cherry S42°W 23.7' 7" Black Cherry N70°E 10.6'

12. D.N.R. Monument 8" R. Maple (clump) S10°W 15.0' 6" Beech N34°E 4.15'
 4" R. Maple S27°E 25.1' 8" R. Maple N53°W 8.7'

Signed by David B. Babbitt

Date 2-11-86

Surveyor's Michigan License No. _____

RLS 21558