

1. Public Land Survey T 45N R 21W I-4 J-4 K-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 In Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**ALGER
CO.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 10/9, 11/21&27, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4. West 1/4 corner of Section 11. Wood post. Sugar 8" S39°W 29 Lks.
 DO 10" N74°E 14 Lks.

J-4. Center of Section 11. Not prev. est.

K-5. SE sec. cor. of Section 11. Geo. Depew-1917. Set iron from Gov't. field notes.
 (Note: Depew "irons" were usually a pipe & brass cap furnished by Alger County.)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4. Set M.P.O.L. between the NW and SW sec. cors. of Section 11 falls at old fence corner fence N&E.

J-4. Set at the intersection of the N-S and E-W 1/4 lines of Section 11 by closed traverse.

K-5. Found pipe w/brass cap set by Geo. Depew. Re-witnessed as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4. D.N.R. Monument 5" Sugar Maple S65°E 42.1' 10" Sugar Maple N81°W 49.0'
 4" Sugar Maple N9°W 36.7' 6" Sugar Maple S29°W 8.0'

J-4. D.N.R. Monument 8" Sugar Maple N75°E 30.6' 6" (twin) R. Maple S28°W 52.25'
 4" Red Maple S53°E 20.3' 5" R. Maple N57°W 49.1'

K-5. Mon. Pipe w/brass cap. 4" R. Maple S56°W 8.0' 5" B. Cherry N31°W 20.9'
 4" Y. Birch S75°W 21.4' 7" B. Cherry N32°E 10.4'

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No.

RLS 21558