

LAND CORNER RECORDATION CERTIFICATE

ALGER

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY. _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLL- 15 45 N. 21 W. ING IN SECTION _____ T. _____ S., R. _____		5, 7, 11, 12
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 4, 1983, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 5 - North 1/16 Cor. on the N-S 1/4 line of Sec. 15; not previously established.
- 7 - North 1/16 Cor. on the East Sec. line of Sec. 15; not previously established.
- 11 - S.W. 1/16 Cor. (Ctr. of the S.W. 1/4) of Sec. 15; not previously established.
- 12 - South 1/16 Cor. of Sec. 15 on the N-S 1/4 line.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 - Set M.P.O.L. between the N 1/4 Cor. and the Ctr. of Sec. 15.
- 7 - Set M.P.O.L. between the N.E. Sec. Cor. and the East 1/4 Cor. of Sec. 15.
- 11 - Set at the computed Ctr. of the S.W. 1/4 of Sec. 15 by closed traverse.
- 12 - Set M.P.O.L. between the S. 1/4 Cor. and the Ctr. of Sec. 15.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5 - D.N.R. Monument; 9" Tw. Top Cedar - N4°W - 52.7'; 5" Cedar - N81°W - 44.5'; 5" Cedar - N19°E - 79.0'; 4" Cedar - S33°E - 25.0'. Falls 60' South of old grade.
- 7 - D.N.R. Monument; 1/2 Cu. Yd. boulder chiseled + in top of S31°W - 71.1'; 7" H. Maple - S53°W - 24.3'; 7" Balsam - N10°E - 26.15'; 7" Maple - S30°E - 21.6'.
- 11 - D.N.R. Monument; 8" Maple - N22°W - 3.3'; 10" Maple - S64°W - 6.35'; 9" Bl. Cherry - S24°E - 26.35'; 7" Maple - N87°E - 21.35'.
- 12 - D.N.R. Monument; 4" Maple - N65°W - 12.4'; 5" Cedar - N25°E - 63.8'; 7" Cedar - S50°E - 59.4'; 6" Cedar - S31°W - 67.2'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: