

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>11</u> T. <u>45N</u> N. S., R. <u>21W</u> E. W.		<u>J-5; K-4; K-3.</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER
COUNTY

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 22, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- J-5. South 1/4 cor. of Section 11. Wood post. Sugar 12 S41W, 15 Lks.
Maple 14 N24E, 15 Lks.
- K-4. East 1/4 corner of Section 11. Wood post. Elm 18 S5E, 25 Lks.
Sugar 8 N50W, 3 Lks.
- K-3. NE section corner of Section 11. Wood post. Elm 12 S79W, 21 Lks.
Sugar 12 N44E, 24 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-5. Set M.P.O.L. between the SW and SE section corners of Section 11.
- K-4. Set M.P.O.L. between the NE section corner and the SE section corner of Section 11.
- K-3. Set by double prop. to the G.L.O. record using section corners one mile east and one mile south and 1/4 cors. 1/2 mile west and 1/2 mile north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5. D.N.R. Monument	K-4. D.N.R. Monument	K-3. D.N.R. Monument
3" aspen S78°E 18.0'	7" sugar maple S44°W 47.9'	7" Balm of Gilead N56°E 4.0'
6" r. maple S9°W 22.2'	6" sugar maple N51°W 45.0'	8" Aspen S49°E 12.7'
4" r. maple S45°W 28.0'	4" sugar maple N5°W 41.6'	9" Balm of Gilead S53°W 6.6'
4" r. maple S85°W 22.0'	7" sugar maple S6°E 27.9'	5" Aspen N56°W 26.65'

SIGNED BY

David B. Babbitt

DATE

9-26-85

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)