

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLL- ING IN SECTION <u>11</u> , T. <u>45N</u> N. S., R. <u>21W</u> E. W.		<u>16; 15; 2.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*ALGER  
COUNTY*

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 7, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

16. E 1/16 cor. on the south section line of Section 11. Not previously established.
15. West 1/16 on south section line of Section 11. Not previously established.
2. East 1/16 cor. on the north section line of Section 11. Not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

16. Set M.P.O.L. between the S 1/4 cor. and the SE section corner of Section 11.
15. Set M.P.O.L. between the SW section corner and the S 1/4 corner of Section 11.
2. Set M.P.O.L. between the NE section corner and the North 1/4 corner of Section 11.  
A 1-1/4" pipe was found N11°W 24.25 from this point but it is of unknown origin and does not fit the true 1/16 cor. position. Could be on road R.O.W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |  |
|---|---|--|
| 16. D.N.R. Monument<br>3" sugar maple S42°W 29.3' | 15. D.N.R. Monument<br>4" sugar maple S82°E 52.7' | 2. D.N.R. Monument<br>5" sugar maple S15°W 74.6' |
| 10" sugar maple S67°W 35.8'                       | 5" sugar maple S2°W 23.4'                         | 5" sugar maple S67°W 70.4'                       |
| 4" b. Cherry S78°W 39.3'                          | 7" sugar maple S60°W 45.2'                        | 4" sugar maple N13°E 51.9'                       |
| 9" red maple N85°W 43.8'                          | 5"(twin) sugar maple N74°W 57.6'                  | 4" aspen N80° -21.6'                             |

SIGNED BY

*David B. Babbitt*

DATE

9-26-85

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: