

Alger

LS. 21-1-80
8-26-80

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>21</u> E. W.	<u>I-5, J-7, K-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 5 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-5 N.W. Section corner, Section 14; set by George Depew in 1915 from original bearing trees. 1 1/2" pipe with brass cap stamped with section, town and range numbers, no N.B.T.'s.
- J-7 South 1/4 corner, Section 14; set by George Depew in 1917. 1 1/2" pipe with brass cap stamped with section, town and range numbers, no N.B.T.'s.
- K-7 S.E. Section corner, Section 14; set by George Depew in 1917. 2" capped pipe stamped with town, range and section numbers, no N.B.T.'s.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-5 Found pipe and brass cap set by George Depew in 1915. Old fence in line south. Re-witnessed as found.
- J-7 Found 1 1/2" pipe with brass cap - set by George Depew in 1917. Old fence in line south. Re-witnessed as found.
- K-7 Found 2" capped pipe with township, range and section numbers stamped on the cap. Set by George Depew in 1917. Re-witnessed as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-5 1 1/2" pipe & 3" brass cap; 9" Maple - N42°E - 42.2'; 5" Maple - N49°W - 57.7'; 8" Maple - S61°W - 15.8'; 6" Ironwood - S50°E - 10.0'; centerline E-W road - North - 15'.
- J-7 1 1/2" pipe & 3" brass cap; 5" Bl. Cherry - N20°E - 18.0'; 6" Balsam - S75°W - 25.0'; 7" Maple - S4°W - 20.6'; 4" Maple - S85°E - 25.4'.
- K-7 2" capped pipe; 9" Maple - S35°W - 17.5'; 12" Tw. Maple - N52°W - 20.1'; 6" Maple - N10°W - 22.7'; 7" Maple - N88°E - 9.6'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 8-26-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558