

B.M.D.
8-26-80

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>21</u> E. W.	<u>H-5, H-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on August 5 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-5 North $\frac{1}{4}$ corner - Section 15. Set by George Depew in 1916 from original bearing trees. $1\frac{1}{2}$ " pipe with brass cap stamped with section, town and range numbers. No N.B.T.'s.
- H-7 South $\frac{1}{4}$ corner - Section 15. Set M.P.O.L. by George Depew in 1916. $1\frac{1}{2}$ " pipe with brass cap stamped with section, town and range numbers. No N.B.T.'s.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-5 Found $1\frac{1}{2}$ " pipe set by George Depew in 1916. Brass cap has been broken off. Old fence in line south. Set D.N.R. monument beside his pipe.
- H-7 Found pipe and brass cap set by George Depew in 1916. Pipe badly bent. Set D.N.R. monument over the bottom of Depew's pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-5 1" pipe, 4" aluminum cap buried in road; 4" Spruce - S20°W - 37.2'; 4" Cedar - S2°W - 46.7'; 7" Cedar - S57°E - 94.3'; Power pole - N65°W - 55.9'; Centerline E-W road - South - 6'.
- H-7 1" pipe, 4" aluminum cap buried in road; 7" Maple - N53°W - 49.6'; 7" Y. Birch - N28°W - 36.2'; 8" Maple - N49°E - 41.8'; Power pole - S1°W - 26.7'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 8-26-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558