

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 6-21-1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-248

Herald W. Coulson
 Chairman
 For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>Alger</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>45N</u> R <u>21W</u> | <u>C1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded July 15, 1994
 at 8:00 o'clock A. M., and
 Recorded in Liber 4 of Cor. Rec.
 on Page 248

Herald W. Coulson
 Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. James, in a field survey on September 28, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C1: P.L.S., John Burt, DS, 1841. Sugar 12, Cor of Secs, 31 & 32. Sugar 18, N.40 W., 32. Sugar 18, S.65 E., 10 links. Minneapolis, St. Paul and Sault Ste. Marie Railroad Right of Way Map, October 27, 1902. Corner noted 1104 feet East of centerline of railroad right of way. Edwin Swan, R.L.S., 1948 and 1949, Alignment notes for Eben-Trenary road, Alger County Road Commission. Standard Alger County Corner, 14" below road surface, at centerline of road intersection. P.Pole, N.50 E., 43.5 feet - Corner fence post, N.57 W., 36.1 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C1: At the centerline of the intersection of Tunteri and Eben-Trenary roads found 1/2" rebar flush with asphalt surface, could not identify from reference objects, objects destroyed. Removed rebar and with locator determined that A.C. Standard was deep or all that remains is base plate. Reaction on locator was weak and centralized. Dug small hole through asphalt to a depth of 24" and tone reaction on locator consistently got better the deeper the probe. It was determined that all that remains is the baseplate of A.C. monument, and the roadbed has been raised over the course of the years. Location indexes well with A.C. Road Commission location as shown on alignment plans. Installed monument and established reference points, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C1: Installed 5/8" x 18" rebar w/3 1/4" Alum. cap stamped to I.D. corner position, grouted in concrete. Est. reference points and reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Anchor Pole, N.52W., 42.44 feet, "BT". Power Pole, N.46 E., 48.34 feet, "BT". Gas Line Marker Post, S.68 E., 84.93 feet. Maple 18", S.77 W., 50.33 feet "BT".

Signed by Robert L. James
 Surveyor's Michigan License No. 25849

Date 1 June 1994