

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-298

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 45N R 21W	C8
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
E. 9:00 a.m.

**SURVEY &
REMONUMENTATION APR 20 1995**

DONALD W. KINNUNEN
EC

MAY 10 1995

COMMISSION Register of Deeds Stamp & File Number

I, Robert L. Jaaros, in a field survey on December 07, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C8: PLS-Zelotes B. Searls, DS, 1850, Set Or. Section Post- Sugar 18", S.25 E., 6 links, Sugar 30", N.45 W., 35 links. Minneapolis, St. Paul and Sault Ste. Marie Railroad Right of Way Map, October 27, 1901, corner noted as being 42 feet west of the centerline of the railroad right of way. County survey notes at the Alger County Road Commission book number 18, Geo. L. Depew, CS, November 09, 1917, placed iron on true line between section corners north and south. Corner lies 46.5 feet west of the centerline of the Soo Line railroad tracks. No references given., Alignment notes for the Eben-Trenary Road, Alger County Road Commission, Edwin Swan, RLS, 1948, Corner position shown with no measurements or monument. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C8: Found 1 3/4" GIP with 3 1/4" Brass cap marked to identify corner position, dated Nov. 9, 1917 at the intersection of fences N, S, and W. Measured Alger County Road Commission station distances along the Eben-Trenary Road to locate corner position. Corner position checks well with record distances. Corner position lies 47.3 ft. West of centerline of old Railroad Grade and 122.5 West of the centerline of the Eben-Trenary Road. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C8: Stamped P.A. 345 in existing brass cap G.I.P. monument. Established reference tree w / BT signs, blazed, scribed and painted. Set PK nail for measure w/ Alum. I.D. washers in the following reference tree. Set six foot long steel fence posts as witness references. Steel Witness Post with sign, N.34 W., 12.12 feet, Steel Witness Post with sign, N.52 E., 36.41 feet, Steel Witness Post with sign, S.58 E., 31.45 feet, Steel Witness Post with sign, S.32 W., 1.5 feet, Maple 12", S.05 W., 77.35 feet, "1/4s BT". All bearings are magnetic.

Signed by Robert L. Jaaros
Surveyor's Michigan License No. 25849

Date 12 April, 1995