

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Harold W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-299

For corners in
Alger

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 21W

C9

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

**SURVEY &
REMONUMENTATION**

MAY 10 1995

COMMISSION

FILED

E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
EG

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on December 07, 1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C9: PLS-Zelotes B. Searls, DS, 1850, Set post corner of sections 19,20,29 & 30 - Y. Birch 18", S.62 W., 27 links, Fir 8", N.80 E., 17 links. Minneapolis, St. Paul and Sault Ste. Marie Railroad right of way map, October 27, 1901, corner noted as being 37.5 feet west of the centerline of the railroad right of way. Geo. L. Depew, CS, 1917. Placed iron corner on line at equal distance and 37 ft. west of Soo Line R/R track according to their survey. No references given., Geo. L. Depew, CS, 1919 alignment notes. Corner position shown 112 ft. west of centerline of road. No references given., Edwin Swan, RLS, 1948, alignment notes for the Eben - Trenary road, Alger County Road Commission. Corner is standard Alger County brass capped monument and is 113.1 feet west of the centerline of the Eben - Trenary road. No reference were given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C9: Found 1 3/4" GIP broken off at ground line, Brass cap gone. Measured Alger County Road Commission station distances along the Eben-Trenary Road to locate corner. Corner position checks well with record distances. Corner position lies 37.5 ft. west of the centerline of an old railroad grade and 114 ft west of the centerline of the Eben-Trenary Road. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C9: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. cap over remains of GIP. Cap stamped to identify corner position. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Aluminum I.D. washers in the following reference trees. Set six foot long steel fence posts as witness references. Spruce 6", S.03 W., 48.06 feet, "S30 BT". Balsam Fir 4", S.73 E., 57.75 feet, "S29 BT", Steel Witness Post with sign, N.64 E., 61.0 feet, Steel Witness Post with sign, N.21 W., 15.43 feet, Steel Witness Post with sign, S.57 W., 2.2 feet. All bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by

Robert L. Jamros
25849

Date

12 April, 1995

Surveyor's Michigan License No.