

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 315 of
 P.A. of 1990 On 4-8-1995

Merald W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-301

For corners in

Alger
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 21W

**SURVEY &
 REMONUMENTATION**

FILED
 RE 9:00 a.m.

APR 20 1995

2. Property Controlling
 in Section

S _____ T _____ R _____
 S _____ T _____ R _____

MAY 10 1995

DONALD W. KINNUNEN
 REG.

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11		●											
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on December 20, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C11: PLS-Zelotes B. Searls, DS, 1850, Set post corner of sections 29,30,31 & 32 - Fir 10", S.54 E., 5 links, Y.Birch 32", N.30 W., 15 links. Minneapolis, St. Paul and Sault Ste. Marie Railroad right of way map, October 27, 1901, Shows corner as being 16 feet west of the centerline of the railroad right of way. From Alger County Road Commission Alignment Drawing for Limestone Township Road (Now Eben-Trenary Rd.), July 1919. Section Corner 91 ft. west of intersection of road centerline. A.C.R.C., Geo. L. Depew, CS, 1919 alignment notes. Southwest corner of Section 29, 91 ft. west of centerline of intersection of roads. Railroad 75 ft. west of centerline of intersection of roads. No references given. Edwin Swan, RLS, 1948, alignment notes for the Eben - Trenary road, Alger County Road Commission. Shows corner position with no material given. Measurement ties are shown from the centerline road intersection, west 92.1 ft. and from centerline railroad tracks, now just a grade, west 16 ft. Measurement tie shown from an iron 35.9 feet west of the centerline intersection to section corner, 56.2 ft. No references were given. M.D.S.H., F.A.S. Project, 1971. Section corner 92.1 ft. west of centerline road intersection. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C11: Found 2" GIP with pipe cap 13" below road surface. Measured Alger County Road Commission station distances along the Eben-Trenary Road to locate corner. Corner position checks well with record distances. Corner position lies 92.05 ft. west of centerline of the Eben-Trenary Road and 56.30 ft. west of existing 3/4" pipe (A.C.R.C.Align.) and 16 ft. west of centerline of old Railroad grade. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C11: Set 5/8" x 12" Rebar w/ 3 1/4" Alum. cap over top of existing 2" iron pipe. Stamped cap to identify corner position. Esablished the following reference objects. NE Cor. Concrete foundation town hall building, N.31 W., 134.07 feet, SE Cor. Concrete foundation of old commercial building, S.26 W., 97.33 feet, P.Pole, S.60 E., 63.63 feet, 'PK w/ Alum. I.D. washer for measure', Easterly 4" Elm of twin Elm 4" & 5", N.46 E., 50.04 feet, 'BT Signs & PK w/ Alum. I.D. washer for measure', 92 feet west of the centerline of the Eben-Trenary road. All bearings are magnetic.

Signed by Robert L. Jamros
 Surveyor's Michigan License No. 25849

Date 12 April, 1995