

Approved by Alger County
Land Survey Commission
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-302

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>21W</u>	<u>C13</u>	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

FILED
E 9:00 a.m.
APR 20 1995
DONALD W. KINNUNEN
EG
Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION**
MAY 10 1995
COMMISSION

I, Robert L. Jamros, in a field survey on December 07, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C13: PLS-William A. Burt, DS, 1841, Set post corner of sections 31 & 32 - Hemlock 16', N.28 E., 30 links, Maple 16', N.41 W., 63 links. Minneapolis, St. Paul and Sault Ste. Marie Railroad right of way map, October 27, 1901, indicates corner as being 47 feet east of the centerline of the railroad right of way., A.C.R.C., Geo. L. Depew, CS, 1919 alignment notes., Section corner 22 ft. W. and centerline of Soo Line R/R 115 ft. W. No references given., Edwin Swan, RLS, 1948, alignment notes for the Eben - Trenary road, Alger County Road Commission. Corner is a standard Alger County brass capped monument and is 52.8 feet east of the centerline railroad track and 30 ft. west of the centerline of the Eben-Trenary Road. No references given. CCI Forestry Division, Land and Timber Examination Report, R.J. Brotherton, RLS, 1955, notes corner as a standard Alger County brass cap monument. No references given. M.D.S.H., F.A.S. Project 1971., Section corner 30 ft. W. of centerline of road and centerline of Railroad 52.8 ft. W. of Section corner. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C13: Found 1 3/4" GIP with 3 1/4" Brass Cap marked to identify corner position, dated Sept. 15, 1917. Measured Alger County Road Commission station distances along the Eben-Trenary Road to locate corner. Corner position checks well with record distances. Corner position lies 52 ft. east of the centerline of an old railroad grade and 30.8 ft. west of the centerline of the Eben-Trenary Road. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C13: Stamped P.A. 345 in existing brass capped galvanized iron pipe monument. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Spruce 16", N.34 1/2 E., 116.75 feet, "No scribing", Spruce 12", S.22 W., 54.05 feet, "S6 BT", P.Pole, S.85 E., 64.20 feet, "BT", Maple cluster 6", N.65 W., 26.29 feet, "S31 BT", Steel witness post with Survey marker sign, S.42 W., 1.4 feet. All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
Surveyor's Michigan License No. 25849