

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 6-21-1994

Gerald W. Carlson
Chairman
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-252

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>21W</u>	<u>F5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded July 15, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Cor. Rec.
on Page 252

David W. Kinnaman
Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on July 22, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F5: P.L.S., Z.B. Searls, DS, 1850. Set qr. sec. post. Sugar 24, S.30 W., 33 links. Sugar 26, N.12 E., 18 links. Gerald W. Carlson, R.L.S., August 1979, corner indicated by survey notes in A.C. Road Commission records. No accessories given. Set 5/8" x 18" Iron w/R.L.S. cap. Found 3" square wood stake and bent 1 1/2" iron pipe w/brass cap and set 5/8" iron between stake and pipe. Established reference objects, P. Pole, N.44 E., 47.17 feet, 34" Elm, S.73 E., 82.78 feet, 22" Maple, S.30 W., 57.51 feet, 28" Maple, S.73 W., 83.68 feet. Recorded in filing No. 276, Alger County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F5: Found 5/8" rebar and remains of 2" G.I.P., both badly bent, and remains of 3" square wood stake, identified by recorded reference objects. Corner position is on centerline of East-West and North roads. Straightened 2" G.I.P. and cut off 6" below road surface. Of the recorded witnesses the 34" Elm is gone. Installed a new monument in centerline of hole in 2" G.I.P. and established new reference points and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F5: Installed 5/8" x 18" rebar w/3 1/4" Alum. cap, stamped to I.D. corner position, inside remains of 2" G.I.P. Renewed existing and est new reference trees w/BI signs and scribed. Set PK nails for measuring w/brass I.D. washers. Ex. Power Pole, N.42 E., 47.0 feet., "BT". Ex. Maple 24", S.29 W., 57.73 feet. Ex. Maple 30", S.71 W., 83.93 feet. Sur. Marker Sign post, S.48 E., 43.89 feet. Sur. Marker Sign Post, N.45 W., 47.90 feet.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 1 June, 1994