

Arnold Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

5-18

For corners in

ALGER

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 21W G1

T 46N R 21W G13

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Section

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED

TIME 2:00 p.m.

MAR 31 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on September 18, 1996, 19____,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

T. 46N. R. 21W. G13

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G1: PLS - John Burt, DS, 1841, Set post cor. of Secs. 33 & 34 * Sugar 14, N.12 E., 14 lks. * Sugar 9, N.60 W., 40 lks. **** Z.B. Searis, DS, 1850. * Post, Sugar 26, S. 56 W., 21 lks. * Sugar 8, S.46 E. 34 lks. **** Geo. L. Depew, CS, 1917. * Placed stand. iron cor. **** Cor. shown on MDSH State Trunkline Rd. Plans at Alger Co. Road Comm. * Surveyed and mapped by G.L. Depew, CS, 1919. * No wit. or mon. material shown. **** M.S.H.D., 1959 Proj., Munising-Chatham Rd. * Cor. position shown at hwy. sta. 536+91.38. * Iron mon. in Mon. box on survey CL. **** Herbert L. Fluharty, RLS, 1975. * Fd. 3/4" Iron bar at CL inter. M-94 & M-67 in Mon. box. * T.P., N.70 W., 71.08' * P.P., S.58 W., 67.07' * P.P., S.63 E., 96.19' * Recorded in L.1, P.76, Alger Co. Records. **** Robert L. Jamros, RLS, 1990. * Alger Co. Rd. Comm. Proj. for the rehabilitation of Tunteri Rd. Exist. 3/4" Iron bar recovered. * ACRC Files **** Robert F. Cambensy, R.L.S., 1993. * Fd. 3/4" iron pin w/ 1 1/4" sq. top in mon. box, CL of inter. of Hwy. M-94 & Hwy. M-67. * Replaced fd. 3/4" iron pin w/ 5/8" x 18" Rebar w/ 3 1/4" Alum. cap, stamped to identify cor. position. * S.E. cor. of conc. culv. hdwl, S.31 E., 69.26' * S.W. cor. of conc. culv. hdwl, * P.Pole, N.72 E., 295.53'to nail. * P.Pole, N.27 W., 132.11'to nail. * L.4, P.210, A.C. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G1: Found 3 1/4" Bernstein Aluminum cap on 5/8" Rebar, stamped to identify corner position in Monument box at centerline of intersections, M-94 and M-67. * Measurements to corners West and East are 2638.71 and 2636.59, respectively. * Monument in box at existing corner position is accepted as the best available evidence of the position of the original corner.

**SURVEY &
REMONUMENTATION**

AUG 15 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G1: Accepted monument at existing corner position as found. Verified existing witness of the 1993 report. * Southeast corner of concrete culvert headwall, S.31 E., 69.26 feet. * Southwest corner of concrete culvert headwall, S.26 W., 66.86 feet. * P. Pole, N.72 E., 295.53 feet, existing nail and washer. * P. Pole, N.27.W., 132.11 feet, existing nail and washer. * All bearings are magnetic.

Signed by

Robert L. Jamros

Surveyor's Michigan License No.

25849

Date

25 March, 1997

