

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 6-21 1994

Marcus W. Curran
 Chairman
 For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-253

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>21W</u>	<u>H3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded July 15, 1994
 at 8:00 o'clock A. M., and
 Recorded in Liber 4 of Cor. Rec.
 on Page 253

D. W. Kimmner
 Alger County Register of Deeds

Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on July 22, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5			4		3		2		1
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H3: P.L.S., Z.B. Searls, DS, 1850. Set qr. sec. post. Sugar 18, S.41 W., 14 links. Sugar 20, N.64 E., 14 links. David Babbitt, R.L.S., October 1985. Set D.N.R. monument in centerline of East-West road and in line with old fences north and south, established reference objects, 4" Balsam Fir, S.08 E., 40.7 feet, 6" Sugar Maple, S.35 E., 56.55 feet, 3" Cedar, N.19 W., 59.2 feet, 9" Cedar, N.61 E., 99.3 feet. Recorded in filing No. 212, Alger County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H3: Found D.N.R. monument, identified by recorded reference objects, badly bent and cap missing on centerline of East-West road in line with old fences North and South. Of the recorded witness points, all remain in tact. Installed new monument 10" below road surface in the centerline of hole remaining from D.N.R. monument. Existing reference points brought up to current standards and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H3: Installed 5/8" x 18" rebar w/3 1/4" alum. cap, stamped to I.D. corner position, in centerline of hole remaining from DNR monument. Renewed existing reference trees w/BT signs, blazed and painted. Set PK nails for measuring w/brass I.D. washers. Ex. Balsam Fir 8", S.08 E., 40.63 feet, "1/4S-NBT". Ex. Maple 7", S.35 E., 56.53 feet. Ex. Cedar 12", N.61 E., 99.51 feet. Ex. Cedar 5", N.21 W., 59.48 feet, "1/4S-NBT".

Signed by Robert L. James
 Surveyor's Michigan License No. 25849

Date 1 June, 1994