

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 6-21 1994

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-254

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>21W</u>	H5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded July 15, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Cor. Rec.
on Page 254

Donald W. Kinnaman
Alger County Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jarros, in a field survey on July 22, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H5: P.L.S., Z.B. Searls, DS, 1850. Set qr. sec. post. Cedar 10, S.57 W., 14 links. Cedar 8, N.22 E., 30 links. David B. Babbitt, R.L.S., August 1980. Found 1 1/2" pipe set by George Depew in 1916. Brass cap has been broken off. Old fence in line South. Set D.N.R. monument beside his pipe. Established reference objects, 4" Spruce, S.20 W., 37.2 feet, 4" Cedar, S.02 W., 46.7 feet, Power Pole, N.65 W., 55.9 feet, 7" Cedar, S.57 E., 94.3 feet, Centerline E-W road, South, 6 feet. Recorded in filing No. 408, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H5: Found 1" G.I.P., identified by record reference objects, bent, pulled up and flat. Excavated around 1" G.I.P. and found remains of 2" G.I.P., Alger County standard monument, and hole made by 1" G.I.P. of the recorded witness points, all remain intact. Corner lies 6 feet South of centerline of East-West road. Installed new monument 8" below road surface in the centerline of remains of 2" G.I.P. Existing reference points brought up to current standards and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H5: Installed 5/8" x 18" rebar w/3 1/4" Alum cap, stamped to I.D. corner position. Renewed existing reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Spruce 8", S.18 W., 37.60 feet. Ex. Power Pole, N.66 W., 56.26 feet, "BT" Ex. Cedar 5", S.01 E., 46.70 feet, "1/4S-NBT". Ex. Cedar 8", S.59 E., 94.70 feet, "1/4S-NBT".

Signed by Robert L. Jarros
Surveyor's Michigan License No. 25849

Date 1 June, 1994