

Approved by Alger County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of  
 P.A. of 1990 On 4-8-1995  
Donald W. Carlson  
 Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

4-296

For corners in  
Alger  
 (County)

Located In: \_\_\_\_\_  
 Corner Code # \_\_\_\_\_

1. Public Land Survey T 45N R 21W H7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

MAY 10 1995

**COMMISSION**

FILED  
 E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN  
 Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on December 06, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

H7: PLS-Zelotes B. Searls, DS, 1850, Set Or. Section Post- Fir 10", S.24 E., 28 links, Sugar 12", N.44 W., 17 links. Alger County Records, George Depew, County Surveyor, 1916, Set Pipe w/ Brass Cap mid-point on line between section corners East and West. No references given. David B. Babbit, RLS, 1980, Found pipe and brass cap set by George Depew in 1916. Pipe badly bent. Set D.N.R. monument over bottom of Depew's pipe and buried in road. References: 7' Maple, N53W., 49.6 ft., 7' Y.Birch, N28W, 36.2 ft., 8' Maple, N49E., 41.8 ft., Power Pole, S01W., 26.7 ft., Filing No. 408, Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H7: Found D.N.R. Monument with 4" Alum. Cap marked to identify corner position, 4.5 ft. south of centerline of gravel road, 5' deep. RLS no. 21558, Babbit stamped in cap. Verified existing references and established additional references. Corner position is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H7: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Renewed existing reference trees w/ BT signs, blazed, scribed and painted. Set Pk nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. P.Pole, S.03 W., 27.27 feet, "BT", Ex. Maple 8", N.50 W., 49.78 feet, "NBT", Ex Y.Birch 9", N.25 W., 36.47 feet, "NBT", Maple 6", N.56 E., 56.73 feet, "1/4s BT", Corner of Cedar Hedge-Cedar 6", S.31 E., 31.01 feet, "PK Only". All bearings are magnetic.

Signed by Robert L. James  
 Surveyor's Michigan License No. 25849

Date 12 April, 1995