

Approved by Alger County
Land Survey Re-monumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Sheild Workson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-293

For corners in
Alger
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>45N</u> R <u>21W</u> | <u>11</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

**SURVEY &
REMONUMENTATION**
MAY 10 1995
COMMISSION

FILED
9:00 a.m.
APR 20 1995
DONALD W. [unclear]
REGISTER [unclear]
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on December 08, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

11: PLS-John Burt, DS, 1841, Set post corner of section 34 & 35 - Cedar 12', N.11 E., 13 links, Cedar 12", N.82 W., 15 links. Corner shown on M.S.H.D. State Trunkline Road Plans at the Alger County Road Commission. Surveyed and mapped by G.L. Depew, CS, 1919, No references or monument material shown or given. M.D.S.H., 1959 Project, Munising - Chatham Road. 1 1/2" Iron Pin in monument box to be adjusted on this project. References: Iron Pipe, S38E., 46.56 ft., Iron Pipe, N45W., 47.66 ft., Fence Post, N33E., 48.66 ft., 10.8 ft. east of centerline of County Road north. Gary E. Koepke, RLS, 1990, Found boat spike in monument box near the centerline of state highway M-94 at county road to north. References: N20E., 72.19 ft., MDOT Tag in top of Guard Post., South, 75.17 ft., Top centerline of concrete R/W marker., N70W., 124.57 ft., MDOT Tag in P.P., N10W., 65.36 ft., MDOT Tag in Stop Sign Post., Filing No. 4-75, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11: Found Boatspike in monument box 0.9 ft. north of centerline of State Highway M-94 and 6.0 ft. E. of centerline of County Road to north. Verified witnesses of the 1990 report to be in agreement with corner position. Stationing on the 1919 road plans of G.L. Depew gives a distance from the corner to the east of 5,289 ft. By appearances in the field the highway has been lifted and the intersections of county roads improved. Normal practices of such an improvement is not to disturb existing monuments but rather lift the position to a new grade with another marker such as a boatspike. The boatspike found is accepted as being a result of normal practices. Established new references. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11: Set 5/8" x 18" Rebar w/ 3 1/4" Alum. Cap in monument box next to existing boat spike. Stamped cap to identify corner position. Established reference trees and or reference objects w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees or objects. PK nail w/ Alum. washer in SW corner of west conc. headwall on culvert, N.21 W., 80.27 feet, PK nail w/ Alum. washer in SE corner of east conc. headwall on culvert, N.21 E., 74.10 feet, Cedar 4", S.43 W., 74.67 feet, "S3 BT", Balsam Fir 6", S.31 E., 76.67 feet, "S2 BT". Corner lies six feet east of the centerline of Finns Spur road. All bearings are magnetic.

Signed by Robert L. Jamros Date 12 April, 1995
Surveyor's Michigan License No. 25849