

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 6-21 1994

Merrill W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-256

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>21W</u>	<u>15</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded July 15, 1994
at 8:00 o'clock A. M., and
Recorded in Liber 4 of Cor. Rec.
on Page 256

Merrill W. Carlson
Alger County Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on July 22, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I5: P.L.S., Z.B. Searls, DS, 1850. Set post cor. of Sec's 10, 11, 14 & 15. Y. Birch 18, S.79 W., 6 links. Sugar 12, N.76 E., 33 links. George Depew, C.S., 1915, set iron corner from government notes. David B. Babbitt, R.L.S., August 1980. Found pipe and brass cap set by George Depew in 1915. Set from original Bearing trees. Old fence in line South. Rewitnessed as found, 9' Maple, N.42 E., 42.2 feet, 5' Maple, N.49 W., 57.7 feet, 8' Maple, S.61 W., 15.8 feet, 6' Ironwood, S.50 E., 10.0 feet, Centerline E-W road, North, 15 feet. Recorded in filing No. 409, Alger County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I5: Found Alger County Standard monument a 2" G.I.P., identified by record reference objects, 30" high, w/3 1/4" Brass cap, stamped to identify corner position. Corner lies 15 feet South of East-West dirt road. Of the recorded witness points, all remain in tact. Stamped P.A. 345 in brass cap. Existing reference points brought up to current standards, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I5: Stamped P.A. 345 in existing Brass Cap G.I.P. monument. Renewed existing reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Ironwood 6", S.53 E., 10.21 feet, "S14-BT". Ex. Maple 12", S.62 W., 16.05 feet, "S15-BT". Ex. Maple 8", N.48 W., 57.90 feet, "S10-BT". Ex. Maple 11, N.40 E., 42.37 feet, "S11-BT". Sur. Marker Sign, South 1.0 feet.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 1 June, 1994