

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8-1995

Donald W. Kinnunen
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-297

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 21W	17
	T _____ R _____	SURVEY &
	T _____ R _____	REMONUMENTATION
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	MAY 10 1995
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	COMMISSION

FILED
E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on December 05, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

17: PLS-Zelotes B. Searls, OS, 1850, Set post corner of sections 14,15,22 & 23 - Sugar 24", S.12 W., 10 links, Sugar 28", N.05 E., 28 links., A.C.R.C., Geo. L. Depew, CS, 1916. Section corner shown on road alignment notes between Sections 15 and 22. References: Maple, 39.5 ft. N., Maple, 43.7 ft. S., Geo. L. Depew, CS, 1917. Placed standard iron corner at northwest corner of Section 23. No references given., Robert L. Jamros, RLS, 1979, Found 1 3/4" Iron pipe with brass cap. Set in Sept. 1917 by George L. Depew, in good condition. References: Elm 8", N.61 W., 27.9 ft., Maple 8", S.06 W., 16.1 ft., Maple 10", N.27 E., 18.5 ft., Maple 10", S.68 E., 39.1 ft., Filing No. 249, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

17: Found 3 1/4" Brass capped monument marked to identify corner position. Monument set by G.L.D. and H.J.H., Sept. 4, 1917 as indicated on the 1979 corner report. George L. Depew was the Alger County Surveyor of that time period. Verified existing witnesses of 1979 report to corner position and established additional witness. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

17: Stamped P.A.345 in existing cast steel brass capped monument. Renewed existing and established new reference trees w/ BT signs and paint. Set PK nails for measure w/ Alum. I.D. Washers in the following reference trees. Ex. Maple 13", N.33 E., 18.45 feet, "Face Blz", Ex. Maple 13", S.63 E., 39.04 feet, "Face Blz", Ex. Twin Maple 8" & 10", S.12 W., 16.21 feet, "Face Blz", Maple 14", N.57 W., 66.08 feet, "S15 BT". All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April, 1995