

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alger
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------------------|
| 1. Public Land Survey | T <u>45N</u> R <u>21W</u> | K1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | <u>SURVEY &</u> |
| | T _____ R _____ | <u>REMONUMENTATION</u> |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | <u>MAY 10 1995</u> |
| | S _____ T _____ R _____ | _____ |

4-295

FILED
E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
REGISTER
Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on December 08, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K1: PLS-William A. Burt, DS, 1841, Set post cor. of Sec. 1 & 2 - Sugar 16", N.57 E., 46 lks, Sugar 7", N.45 W., 17 lks., Walter W. Gleason, CS, 1914. SE corner of Sec 35, T.46N., R.21W., Iron Cor. Ref: 12" Maple, S.29 W., 47.5 ft., 16" Maple, S.48 E., 104.2 ft., Geo. L. Depew, CS, 1919 Rd align notes. SE corner Sec 36, T.46N., R.21W., Iron cor at Twp Rd N. No ref given., Cor shown on M.S.H.D. Road Plans at the A C Rd Comm. Surveyed by G.L. Depew, CS, 1919. No ref or mon mat given. M.S.H.D. Project No. 5192(8) for the Munising - Chatham Rd. Oct 16, 1959. 1" Iron pipe in monument box adjusted on this project. Ref as follows, Iron pipe, N.45 W., 47.11', Fen post, S.41 E., 41.72', Fen post, S.(blank)W., 37.08', On centerline of Cty Rd N. M.D.O.T. Plans, 1981, call for iron pin in mon box. Gregory W. Asher, RLS, 1982, Fd iron pin in mon box. Ref: P.P., N51E., 108.5 ft., P.P., S34E., 182.5 ft., P.P., S70W., 182.5 ft., P.P., N64W., 167.5 ft. Filing No. 3-80, A C Rec. Gary E. Koepke, RLS, 1991, Fd iron pin in mon box. Ref: N50E., 108.28 ft., Nail in P.P., S30E., 184.54 ft., Tag in P.P., S10W., 182.33 ft., Tag in P.P., N60W., 167.36 ft., Nail in P.P. Filing No. 4-76, A C Rec.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K1: Found 1" Iron Bar in makeshift monument box on centerline of State Highway M-94 at centerline of County Road north and south. Verified witnesses of 1982 and 1991 reports to be in agreement with corner position. Stationing on the 1919 road plans of G.L. Depew gives a distance of 5,289 ft. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K1: Set 5/8" x 18" rebar w/ 3 1/4" Alum. cap along side of 3/4" iron bar in monument box. Stamped cap to identify corner position. Renewed reference objects w/ paint. Set PK nails w/ Alum. I.D. washers for measure in the following reference objects. P.Pole, S.31 E., 184.67 feet, "BT", Ex. P.Pole, S.11 W., 182.41 feet, "BT", Ex. P.Pole, N.59 W., 167.42 feet, "BT", Ex. P.Pole, N.56 E., 108.39 feet, "BT", All existing reference objects have a U.S.F.S. tag at breast height and scribed BT at base of pole. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 April, 1995