

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>J-7, I-6, K-6</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER
CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on October 25 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- J-7 South 1/2 corner; wood post - Cedar 18 - N12°E - 27 lks.; sugar 12 - S33°W - 21 lks.
 - I-6 West 1/2 corner; wood post - Lynn 12 - N60°W - 44 lks; Sugar 18 - S24°E - 23 lks.
 - K-6 East 1/2 corner; wood post - Y. birch 12 - N72°E - 9 lks.; elm 18 - S58°W - 17 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-7 Found iron pipe - not or record - trunk of cedar with old blazes lying on the ground in the general vicinity of N.E. O.B.T. - replaced pipe with D.N.R. mon.
 - I-6 Set M.P.O.L. between the SW and NW section corners of Sec. 14
 - K-6 Set M.P.O.L. between the NE and SE section corners of Sec. 14. A 29" Y. birch with a very old blaze facing this point is N35°W 26.6'.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- J-7 1" pipe, 4" aluminum cap and cedar post; 10" maple - S74°E - 11.25; 5" cedar - S15°E - 56.6
5" cedar - S10°W - 61.0'; 13" maple - N18°W - 16.7'.
 - I-6 1" pipe, 4" aluminum cap and cedar post; 8" cedar - S23°W - 38.3'; 10" cedar - S81°W - 52.3
16" spruce - N80°W - 36.1'; 11" maple - N36°E - 23.75'
 - K-6 1" pipe, 4" aluminum cap and cedar post; 10" cedar - N1°W - 33.95'; 9" cedar - N80°E - 16.1
9" cedar - S15°W - 34.6'; 9" bl. cherry - N73°W - 21.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558