

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

*ALGER  
CO.*

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>F-1</u>
2. PROPERTY CONTROLLING IN SECTION	<u>4</u> , T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 22 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-1 North  $\frac{1}{4}$  corner; wood post; w. pine 30" - N71°E - 1.37 chs.; tamarack 10" - S48°E - 1.23' ch
- 1 West 1/16 corner on north section line; not previously established

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- F-1 Set from stump of orig. b.t. w.p. 30" - N71°E - 1.37 chs. - section of r.r. rail found at S71°W - 1.06 from b.t. stp. - apparently set from said b.t. but at wrong distance.
- 1 Set mid-point on line between the north  $\frac{1}{4}$  corner and the N.W. section corner of Sec. 4

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL 1" pipe, 4" aluminum cap
- F-1 14" w. spruce - S77°E - 127.9'; 7" w. pine - S42°E - 84.7'; narrow guage RR - N71°E - 20.25'; 36" w.p. stp. (o.b.t.) - N71°E - 90.4'
- 1 3" r. maple - S57°W - 49.2'; 6" r. maple - west - 58.0'; 4" b. spruce - N1°W - 32.9'; 8" (dead) B. spruce - N11°E - 1.2'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558