

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>E-4, D-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER
CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 14 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-4 East $\frac{1}{4}$ corner; wood post; tam 5 - N65°E - 19 lks.; tam. 10 - S75°E - 86 lks.
- D-3 North $\frac{1}{4}$ corner; wood post; iron wood 8" - N37°E - 20 lks; sugar 10 - S50°W - 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-4 About 60' east of creek found 3" x 3" sq. cedar post N.E. o.b.t. in place but down with face on top of trunk - upper face plainly scribed " $\frac{1}{4}$ ".
- D-3 Corner set mid-point on line between section corners (with original evidence) $\frac{1}{2}$ mile east and $\frac{1}{2}$ mile west. Fits well with stream west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-4 1" pipe, 4" aluminum cap and cedar post; 12" tam. - N47°E - 10.1'; 6" cedar - N 70°E - 9.6'; 8" stem of tv. cedar - S35°E - 30.4'; 6" cedar - N25°W - 2.1'.
- D-3 1" pipe, 4" aluminum cap; 4" balsam fir - S1°E - 18.0'; 11" b. cherry - S66°W - 10.3'; 9" h. maple - N68°W - 11.8'; 10" h. maple - N51°E - 19.4'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558