

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>B-1, E-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>17</u>	T. <u>45</u> N. S., R. <u>22</u> E. W.	<u>16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ALGER  
CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram--over) were, in a field survey on November 4 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- B-1 North  $\frac{1}{4}$  corner; wood post, sugar 5 - N23°E - 31 lks.; Do 9 - N53°W - 27 lks.
- E-7 Southeast section corner; wood post, tamarack 14 - N40°E - 14 lks.; tamarack 12 - S30°W - 25 lks.
- 16 East 1/16 corner on south section line; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- B-1 Found rock cairn around old fence post with several roofing caps on it. It is very near on a straight line between the N.E. & N.W. sec. cors. and slightly west of the prop. mea. position. It is in an old N-S fence and also falls in line with the centerline of a Co. Rd. north.
- E-7 Found 1 $\frac{1}{4}$ " pipe set by unknown surveyor - replaced with D.N.R. monument.
- 16 Set mid-point on line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- B-1 1" pipe, 4" aluminum cap & cedar post; 7" balsam - S25°W - 39.0'; 12" maple - S74°W - 23.8  
5" balsam - N44°W - 16.2'; 5" balsam - N54°E - 15.2'
- E-7 1" pipe, 4" aluminum cap; b. spruce 4" - N37°E - 22.1'; cedar 5" - S3°E - 19.75'; cedar 5" N70°W - 14.8'; cedar 4" - S55°W - 8.65'
- 16 1" pipe, 4" aluminum cap; B. ash 4" - N43°W 8 10.35'; balsam fir 3" - N74°E - 14.50'; cedar 6" - S45°E - 5.05'; y. birch 20" - S30°W - 3.90'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558